



**Pollution Control Board, Assam**  
**Bamunimaidam : Guwahati-21**

Website: [www.pcbassam.org](http://www.pcbassam.org).

**NOTICE INVITING TENDER**

No. PCBA/G-83/23-24/06

Dated, Guwahati the 1<sup>st</sup> November, 2023

Sealed tenders in single bid system are invited from the Govt./Semi Govt./Board/Corporation and experience Contractors/registered for the following works of Pollution Control Board, Assam. Tenders will be received **up to 3.00 PM on 17-11-2023** and will be opened on the same day at 3.30 PM in presence of intending tenderers or their authorized representatives. In case, the day of submission of the tender happens to be a holiday on account of Govt. notification and tender cannot be received or opened, the tender shall be received up to 3.00 PM & opened at 3.30 PM on the next working day for which no separate communications will be made. BOQ enclosed at **Annexure-B** terms & conditions enclosed at **Annexure-A**.

Name of works	"Renovation of Office Canteen" of Pollution Control Board, Assam, Head Office at Bamunimaidam, Guwahati- 21(Assam).
Earnest Money	Rs. 6,000/-
Last Date & Time for submission of tender paper	Up to 3.00 PM on 17.11.2023
Date & time for opening	At 3.30 PM on 17.11.2023
Time of Completion	30 (Thirty)days

(Shantanu Kr. Dutta)  
**Member Secretary**

Memo No. PCBA/G-83/23-24/06-A,

Dated, Guwahati the 1<sup>st</sup> November, 2023

Copy to:

1. The Member of Central Tender Committee, PCBA for information and necessary action.
2. The Deputy Manager (F & A), Head Office, PCBA for information and necessary action.
3. P.A to the Chairman, PCBA for kind appraisal of the Hon'ble Chairman.
4. Board's Website ([www.pcbassam.org](http://www.pcbassam.org))/Notice Board of the Board's Head Office, PCBA.
5. APS, advertising Pvt. Ltd, for publish the matter in "**Amar Asom**" on 02/11/2023 (one day) in inner page at minimum size.

(Shantanu Kr. Dutta)  
**Member Secretary**



## ANNEXURE-A

### Other Terms & Conditions:

1. Rates should be quoted in the Bill of Quantity (BOQ) furnished in **Annexure-B** in figure and words. If there are variations between the rate of figure and words, the rate quoted in words shall be considered.
2. All pages of the tender document shall be signed and dated at the lower right hand corner by the tenderer or by a person holding power of attorney authorizing him to sign on behalf of the tenderer before submission of the tender.
3. The work shall be completed within 30 (thirty) days from the date of issue of the formal Work Order.
4. The rates shall be inclusive of, forest royalty, cess, octroy, loading & unloading and transportation etc. of all the materials to site. GST should be stated separately in the BOQ.
5. The contractor shall arrange all the plants, equipments, machineries etc. required for the work to site for which no extra charges will be paid.
6. The undersigned reserves the right to accept or reject any or all quotation received hereunder without assigning any reason thereof.
7. Any abnormal rate quoted in the tender will summarily be rejected for which no communication will be made.
8. The Earnest Money shall be paid in the form of Demand Draft/ Banker's cheque drawn in favour of the **Member Secretary, Pollution Control Board, Assam** payable at Guwahati.
9. Defect liability period: 6 (six) months from the date of completion.
10. Documents to be enclosed:
  - i Valied Contractor registration certificate issued by Govt./Semi Govt./Board/Corporation.
  - ii Experience certificates along with work order copy regarding execution of similar works at least 3 nos in last 3 years.
  - iii GST Registration certificate.
  - iv PAN card copy.
11. Any tender submitted without the documents and earnest money mentioned above will be considered as incomplete and the tender will be rejected for which no communication will be made.
12. The EMD of the successful tenderers shall be retained as initial security and EMD of the unsuccessful tenderers shall be refunded after finalizing of the tender.
13. All legal disputes will be subjected to jurisdiction of Guwahati Court only.

  
(Shantanu Kr. Dutta)  
Member Secretary



Pollution Control Board, Assam

**SHORT NOTICE INVITING TENDER**

No. WB/G-83/23-24/06

Dated Guwahati the, 1st Nov, 2023

Sealed tenders are invited for "**Renovation of Office Canteen**" of Pollution Control Board, Assam, For details, please visit Board's website [www.pcbassam.org](http://www.pcbassam.org).

Sd/-

**Member Secretary**



## Bill of Quantities

## ANNEXURE-B

NO.PCBA/G-83/23-24/06

Name of Works: Renovation of Office Canteen of Pollution Control Board, Assam, Head Office at Barmunimaidam, Guwahati- 21(Assam).

Dated Guwahati, the 30<sup>th</sup> October, 2023.

ITEM S NO	DSR NO	DESCRIPTION OF THE ITEMS	QTY	RATE (In Rs.)	AMOUNT	
					In figures	In words
1	4.1.3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-II)) : 4 graded stone aggregate 20 mm nominal size)	2.438m <sup>3</sup>			
2	6.1.3	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level.1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size)	2.16m <sup>2</sup>			
3	5.1.3	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :1:2:4 (1 cement : 2 coarse sand (zone-II)) : 4 graded stone aggregate 20 mm nominal size)	0.700m <sup>3</sup>			
4	5.9.4	Centering and shuttering including strutting, propping etc. and removal of form for :Shelves (Cast in situ)	10.00m <sup>2</sup>			
5	5.22.6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	100kg			
6	11.37.	<b>Item Shifted to Sub Head 8 as item 8.31</b> Providing and laying Ceramic glazed floor tiles of size 300x300 mm(thickness to be specified by	46m <sup>2</sup>			

*H. Barua*

## Bill of Quantities

## ANNEXURE-B

NO.PCBA/G-83/23-24/06

Name of Works: Renovation of Office Canteen of Pollution Control Board, Assam, Head Office at Bammunimaidam, Guwahati- 21(Assam).

Dated Guwahati, the 30<sup>th</sup> October, 2023.

		the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement :4 Coarse sand), Jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement and matching pigment etc., complete.				
7	11.41.2	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 600x600 mm	60.00m <sup>2</sup>			
8	8.2.2.2	Providing and fixing 18 mm thick gang saw cut, mirror polished, pre-moulded and pre-polished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels. Area of slab over 0.50 sqm	3.25m <sup>2</sup>			
9	Non - Schedule	Providing and fixing aluminum work for partitions with extruded built up standard tubular sections/	5.04m <sup>2</sup>			

*HSanki*



## Bill of Quantities

## **ANNEXURE-B**

NO.PCBA/G-83/23-24/06

Name of Works: Renovation of Office Canteen of Pollution Control Board, Assam, Head Office at Bamunimaidam, Guwahati- 21(Assam).

Dated Guwahati, the 30<sup>th</sup> October, 2023.

	d	appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminum sections shall be smooth, rust free, straight, mited and jointed mechanically wherever required including cleat angle, Aluminum snap beading for glazing / paneling, C.P. brass / stainless steel screws and all complete with 12 mm thick Pre-laminated particle board paneling with decorative lamination on one side and balancing lamination on other side and 4 mm thick frosted glazing.				
10	Non - Schedule d	Dismantling & repairing of wall	15.00m <sup>2</sup>			
11	12.45.3	Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/sum (both side inclusive) as per IS : 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm running at the spacing of 1200 mm centre to	24.00sqm			

*Handwritten signature*

NO.PCBA/G-83/23-24/06

**Bill of Quantities**

**ANNEXURE-B**

Name of Works: Renovation of Office Canteen of Pollution Control Board, Assam, Head Office at Bamunimaidam, Guwahati- 21(Assam).

Dated Guwahati, the 30<sup>th</sup> October, 2023.

	<p>centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm centre, with 25mm long dry wall screws @ 230 mm interval, including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25 mm at 230 mm c/c. including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound, jointing tapes, finishing with jointing compound in 3 layers covering up to 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cut-outs made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of the Engineer in Charge but excluding the cost of painting with :12.5 mm thick tapered edge gypsum moisture resistant board</p>				
--	---	--	--	--	--

*Handwritten signature*

**Bill of Quantities**

**ANNEXURE-B**

NO.PCBA/G-83/23-24/06

Dated Guwahati, the 30<sup>th</sup> October, 2023.

Name of Works: Renovation of Office Canteen of Pollution Control Board, Assam, Head Office at Barmunimaidam, Guwahati- 21(Assam).

		required shade (Company Depot Tinted) with silicon additives. 13.48A.1 New work (Two or more coats applied @ 1.43 litre/10 sqm. Over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm.				
<b>Total amount before GST=</b>						
<b>GST</b>						
<b>Total amount before GST=</b>						

*Handwritten signature*

## Bill of Quantities

## **ANNEXURE-B**

NO.PCBA/G-83/23-24/06

Name of Works: Renovation of Office Canteen of Pollution Control Board, Assam, Head Office at Bamunimaidam, Guwahati- 21(Assam).

Dated Guwahati, the 30<sup>th</sup> October, 2023.

12	13.2.1(V-II)	CEMENT PLASTER (IN FINE SAND) 1: 1:4 (1 cement: 4 fine sand)	15.00m <sup>2</sup>			
13	8.3.2	Providing edge moulding to 18 mm thick marble stone counters, Vanitiesetc., including machine polishing to edge to give high gloss finish etc. complete as per design approved by Engineer-in-Charge.Granite work	14.00m			
14	Non Schedules	Door opening & Refitting	2 nos			
15	13.80(V-II)	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	200m <sup>2</sup>			
16	13.43.1(V-II)	Applying one coat of water thinkable cement primer of approved brand and manufacture on wall surface .Water thinkable cement primer	260m <sup>2</sup>			
17	13.48A(V-II)	Finishing walls with 100% Premium acrylic emulsion paint having VOC less than 50 gm/litre and UV resistance as per IS 15489:2004,Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company Depot Tinted) with silicon additives.13.48A.1 New work (Two or more coats applied @ 1.43 litre/10 sqm. Over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm.	60m <sup>2</sup>			
18	13.48A(V-II)	Finishing walls with 100% Premium acrylic emulsion paint having VOC less than 50 gm/litre and UV resistance as per IS 15489:2004,Alkali & fungal resistance, dirt resistance exterior paint of	200m <sup>2</sup>			

*H. Sengupta*